

Magnus Larsson
Danfoss Värmepumpar AB
Box 950
671 29 ARVIKA
Sweden

Test of air-to-water heat pump for EN 14825

(7 appendices)

Work requested

Testing of an air-to-water heat pump in accordance to EN14825:2013, to determine the seasonal coefficient of performance, SCOP. The heat pump was tested for the average climate, and for both low temperature and high temperature applications. Additional test conditions according to EN 14511 were also performed.

Item for testing

Type of heat pump:	Air/Water, fixed capacity type, new heat pump
Manufacturer:	Danfoss Värmepumpar AB
Type designation:	Thermia Atec HP 9
Serial number, heat pump:	086U936026480707
Cold heat transfer medium:	Air
Warm heat transfer medium:	Water
Refrigerant:	R407C, 4.3 kg
Dimensions (width x depth x height):	856 x 510 x 1272 mm
Weight (empty):	131 kg

The heat pump was delivered from the manufacturer to SP's test laboratory in February 2014. No damage could be seen on the unit when visually inspected.

Place and date of testing

The heat pump was installed by SP following the instructions from the manufacturer. The heat pump was tested at SP at the department of Energy Technology during March 2014.

Test methods

The space heating performance of the heat pump was tested in accordance with EN 14825:2013, EN 14511-2:2013 and EN 14511-3:2011. Testing and rating at part load conditions, calculation of seasonal performance and determination of the energy consumption at thermostat off mode, standby mode, off mode, crankcase heater mode and compressor off mode were carried out in accordance with EN 14825:2013. Performance testing was performed for the standard European climate, as defined in EN 14825, average (A) at test points as shown in table 1 and table 2. The heat pump has variable outlet temperature, and a heat curve based on the outdoor temperature. For the test points where the heat pump's heating capacity is higher than what is required, the outlet temperature during the performance test is corrected according to eq. 15 in EN 14825 and the coefficient of performance is corrected, in accordance

SP Technical Research Institute of Sweden

Postal address
SP
Box 857
SE-501 15 BORÅS
Sweden

Office location
Västeråsen
Brinellgatan 4
SE-504 62 BORÅS

Phone / Fax / E-mail
+46 10 516 50 00
+46 33 13 55 02
info@sp.se

Laboratories are accredited by the Swedish Board for Accreditation and Conformity Assessment (SWEDAC) under the terms of Swedish legislation. This report may not be reproduced other than in full, except with the prior written approval of the issuing laboratory.

to EN 14825, using a degradation coefficient, Cc. Heating load less than 100% of the building's heating demand is referred to as part-load ratio.

Table 1 Space heating performance testing and part-load ratio in accordance with table 12 presented in EN 14825 for seasonal performance calculations for average climate (A) and low temperature application.

Average			Outdoor heat exchanger	Indoor heat exchanger
Test point	Part-load ratio ¹	Part-load ratio %	Outdoor air	Inlet/outlet temperatures
			Inlet dry bulb (wet bulb) temperature, °C	Variable outlet °C
A	$(-7-16)/(T_{designh}^2-16^3)$	88	-7(-8)	^a /34
B	$(+2-16)/(T_{designh}-16)$	54	2(1)	^a /30
C	$(+7-16)/(T_{designh}-16)$	35	7(6)	^a /27
D	$(+12-16)/(T_{designh}-16)$	15	12(11)	^a /24
E	$(TOL -16)/(T_{designh}-16)$		TOL	Variable outlet shall be calculated by interpolation or extrapolation from the temperatures which are closest to the TOL. ^a
F	$(T_{biv}^4-16)/(T_{designh}-16)$		T _{biv}	Variable outlet shall be calculated by interpolation from the upper and lower temperatures which are closest to the bivalent temperature.

¹ Formula for calculating the part-load ratio of the building's maximum heating load at a specific temperature condition

² Reference design temperature condition for heating, T_{designh} = -10°C for average climate

³ Outdoor air dry bulb temperature, at this temperature the building's heating demand is zero

⁴ Lowest outdoor air dry bulb temperature at which the heat pump is capable of covering the total heating demand of the building, T_{biv} = +2°C maximum value for average climate

^a With the water flow rate as determined at the standard rating conditions given in EN14511-2 at 30/35 conditions

Table 2 Space heating performance testing and part-load ratio in accordance with table 18 presented in EN 14825 for seasonal performance calculations for average climate (A) and high temperature application.

Average			Outdoor heat exchanger	Indoor heat exchanger
Test point	Part-load ratio ¹	Part-load ratio %	Outdoor air	Inlet/outlet temperatures
			Inlet dry bulb (wet bulb) temperature, °C	Variable outlet °C
A	$(-7-16)/(T_{\text{designh}}^2-16^3)$	88	-7(-8)	^a /52
B	$(+2-16)/(T_{\text{designh}}-16)$	54	2(1)	^a /42
C	$(+7-16)/(T_{\text{designh}}-16)$	35	7(6)	^a /36
D	$(+12-16)/(T_{\text{designh}}-16)$	15	12(11)	^a /30
E	$(\text{TOL} - 16)/(T_{\text{designh}}-16)$		TOL	Variable outlet shall be calculated by interpolation or extrapolation from the temperatures which are closest to the TOL. ^a
F	$(T_{\text{biv}}^4-16)/(T_{\text{designh}}-16)$		T_{biv}	Variable outlet shall be calculated by interpolation from the upper and lower temperatures which are closest to the bivalent temperature.

¹ Formula for calculating the part-load ratio of the building's maximum heating load at a specific temperature condition

² Reference design temperature condition for heating, $T_{\text{designh}} = -10^\circ\text{C}$ for average climate

³ Outdoor air dry bulb temperature, at this temperature the building's heating demand is zero

⁴ Lowest outdoor air dry bulb temperature at which the heat pump is capable of covering the total heating demand of the building, $T_{\text{biv}} = +2^\circ\text{C}$ maximum value for average climate

^a With the water flow rate as determined at the standard rating conditions given in EN14511-2 at 47/55 conditions

The space heating performance of the heat pump was also tested in accordance with EN 14511 and the certification reference HARP, at test points as shown in table 3. Results, with measured and calculated data shown in tabular form, are found in appendix 4.

Table 3. Test conditions for space heating test in accordance to EN 14511 and HARP

Test point	Inlet dry bulb (wet bulb) temperature, °C	Warm heat transfer medium, inlet/outlet temperature, °C
A7/W35	7(6)	30/35
A2/W35	2(1)	a/35
A7/W45	7(6)	40/45

a: Tested with heat transfer media flow rates obtained at test condition A7/W35

Test equipment

The following test equipment was used:

Name	SP inventory no.
Test rig	LV3
Data acquisition system	900 071, 201 417
Electric power meter	901 478, 202 720, 901 995
Flow meters	701 277
Differential pressure sensors	202 865
Dew point sensor	200 428, 200 358
Resistive temperature sensors, Pt 100.	-

Heat pump settings for the space heating performance tests

The heat pump was installed by personnel from SP following the instructions from the manufacturer. The following settings were used during the measurements:

During the performance test maximum heat curve was used to keep the compressor running continuously

There is no internal warm heat transfer medium circulation pump in the unit.

Results from space heating performance testing

The test results given in this report relate only to the specific item tested and under the specific conditions described, with the specific equipment named and at the specified settings. Calculations are based on the results from the laboratory tests according with EN 14825:2013 which in its turn refers to EN 14511:2011 part 3 in a large scale when denoting the test method. The water flow rate was determined at the standard rating conditions given in EN14511-2:2013 at 30/35 conditions for the low temperature application and at 47/55 conditions for the high temperature application. Results are defined according to EN 14825.

The bivalent temperature, T_{biv} , was declared by the manufacturer. At T_{biv} the heat pump is capable of covering the total heating demand of the building. The heating demand of the building, $P_{designh}$, is determined by dividing the heating capacity measured at T_{biv} , by the formula for calculating the part-load ratio at the same temperature condition. For the formula for calculating the part-load ratio see table 1 and 2.

Table 3 $T_{bivalent}$ and $P_{designh}$ for the heat pump tested.

Low temperature application, average climate		High temperature application, average climate	
$T_{biv}, ^\circ C$	$P_{designh}, kW$	$T_{biv}, ^\circ C$	$P_{designh}, kW$
-5	7.24	-4	7.59

The unit was tested for test point E at $-10^\circ C$ for both the low and high temperature application in accordance to EN 14825. EN 14825 states if the declared TOL is lower than $T_{designh}$, it may be assumed that TOL is equal to $T_{designh}$.

Results from capacity tests

Table 4 below presents the total thermal output power, P_H , and the corresponding coefficient of performance, COP, at corresponding test points A-F in table 1 and table 2. The values presented are the results from the laboratory tests according with EN 14825 and EN 14511 for the average climate. The operating conditions are presented in table 1 and table 2.

Table 4 Results from the performance tests.

Test point:	Low temperature application, average climate			High temperature application, average climate		
	P_H (kW)	P_E (kW)	COP	P_H (kW)	P_E (kW)	COP
A	5.52	1.70	3.24	5.23	2.23	2.35
B	6.80	1.78	3.83	6.79	2.14	3.18
C	7.58	1.76	4.30	8.71	2.09	4.17
D	10.44	1.77	5.90	10.16	1.97	5.16
E	4.95	1.70	2.92	4.64	2.30	2.02
F	5.85	1.69	3.47	5.84	2.18	2.69

¹For the test points where the heat pump’s heating capacity is higher than what is required, the outlet temperature during the performance test was corrected according to eq. 15 in EN14825. Please see Appendix 1 for measured test data.

Results for measurements of power consumption during modes other than “active mode”

Table 5 below presents the measurements of the energy consumption at thermostat off mode, standby mode, off mode, crankcase heater mode and compressor off mode. The compressor off mode is needed for the calculation of the Cc-factor which is used for recalculation of COP at the test points where the heat pump’s heating capacity is higher than what is required. Compressor off was therefore measured after test points B-D.

Table 5 Results for power consumption during modes other than active mode

	Low temperature application, average climate	High temperature application, average climate
Thermostat off ¹ (W)	10	3
Standby mode (W)	7	7
Off mode (W)	7	7
Crankcase heater mode ¹ (W)	0	0
Compressor off ² (W), For test point:	Low temperature application, average climate	High temperature application, average climate
B	80	36
C	64	23
D	42	22

¹ In accordance to EN 14825 the standby power consumption is deducted from the measured total energy consumption of the unit during thermostat off mode and during crankcase heater mode.

² Not defined in EN 14825. However, it is needed when calculating the Cc-factor according to eq.18. According to EN 14825, “The electrical power input during the compressor off state of the unit is measured when the compressor is switched off for at least 10 min.” The heat curve was lowered until the compressor stopped. Corrections were made for power input of liquid pump, according to EN14511-3:2011.

Results for SCOP

The results obtained from the testing was used to calculate the values of the seasonal coefficient of performance, SCOP, which are presented in table 6. The results are based on the T_{biv} and $P_{designh}$ presented in table 3.

Table 6 SCOP results for low temperature and high temperature applications.

Low temperature application, average climate			High temperature application, average climate		
T_{biv}	$P_{designh}$	SCOP	T_{biv}	$P_{designh}$	SCOP
-5	7.24	3.70	-4	7.59	3.20

More detailed presentations of the tests, with measured and calculated results shown in tabular form, are found in appendix 1.

Revision

In this revision test results for HARP have been added.

SP Technical Research Institute of Sweden Energy Technology - Building Services Engineering

Performed by

Examined by

Helena Nakos

Johan Larsson

Appendices

1. Result, technical data sheet in accordance to EN 14825
2. Result space heating performance testing, low temperature application
3. Result, space heating performance testing, high temperature application
4. Results, space heating performance testing in accordance with EN 14511 and the certification reference HARP
5. List of components
6. Photographs
7. Uncertainty of measurement
8. Nomenclature

Appendix 1

Results, technical data sheet in accordance to EN 14825

Model name	Thermia ATEC HP 9				
				Low temp. application	High temp. application
Function	Heating		Average "A"	Yes	
Capacity control	Fixed			Yes	
Design load	Heating	Average	P _{designh}	7.24	7.59
Seasonal Efficiency	Heating	Average	SCOP _{on} ¹	3.74	3.23
			SCOP _{net} ²	3.82	3.33
			SCOP ³	3.70	3.20
Heating capacity at outdoor temperature T _j	Heating, Average	T _j = -7 °C	P _H	5.52	5.23
		T _j = 2 °C	P _H	6.80	6.79
		T _j = 7 °C	P _H	7.58	8.71
		T _j = 12 °C	P _H	10.44	10.16
		T _j = bivalent temperature	P _H	5.85	5.84
		T _j = operation limit, -10 °C	P _H	4.95	4.64
Coefficient of performance for heating at outdoor temperature T _j	Heating, Average	T _j = -7 °C	COP	3.24	2.35
		T _j = 2 °C	COP	3.83	3.18
		T _j = 7 °C	COP	4.30	4.17
		T _j = 12 °C	COP	5.90	5.16
		T _j = bivalent temperature	COP	3.47	2.69
		T _j = operation limit, -10 °C	COP	2.92	2.02
Bivalent temperatures	Heating, Average	T _{bivalent}		-5	-4
Operation limit temperatures	Heating, Average	TOL		-10 ⁴	-10 ⁴
Seasonal electricity consumption	Heating, Average	QHE/A		2742	3317
Modes other than "active mode"	Off-mode ⁵			7	7
	Standby mode ⁶			7	7
	Thermostat-off mode ⁷			10	3
	Crankcase heater mode ⁸			0	0
Contact details for obtaining more information	Name manufacturer	Danfoss Värmepumpar AB			
	Address	Snickaregatan 1 671 34 Arvika Sweden			

Appendix 1

¹ SCOP_{on} is the heat pump's average seasonal performance in active mode, presenting the hours the heat pump's heating performance is activated

² SCOP_{net} is the heat pump's average seasonal performance in active mode excluding electricity consumption for thermostat off, standby, off mode, crankcase heating mode and that of an electrical back up heater

³ SCOP is the units total seasonal performance factor representing the whole heating season

⁴ Set to the same value as T_{designh}

⁵ A mode where the unit is completely switched off and is not capable to be reactivated by a control device or a timer

⁶ A mode where the unit is partially switched off and can by a control device or timer be reactivated

⁷ A mode corresponding to the hours with no heating load, but where the heating function of the unit is switched on but the unit is not operational as there is no heating load

⁸ A mode corresponding to the hours where a heating device is activated to avoid refrigerant to migrating to the compressor in order to limit the refrigerant concentration in oil at compressor start

Appendix 2

Results, space heating performance in accordance to EN 14825, average climate and low temperature application

Operating point		1	A	B	C	D	E	F
		30/35	-/34	27,8/-	25,6/-	23,4/-	-/35	-/33,11
	°C	7/6w	-7/-8w	2/1w	7/6w	12/11w	-10/-11w	-5/-6w

Data collection period	<i>min</i>	70	70	180	180	70	70	70
Transient		No	No	Yes	Yes	No	No	No

<i>Temperature</i>		°C						
Heat transfer medium, hot, outlet	t_{w2}	35.0	34.1	31.7	29.9	29.3	35.2	33.2
Heat transfer medium, hot, inlet	t_{w1}	30.0	30.9	27.8	25.5	23.3	32.4	29.8
Dry bulb air temperature	t_{a5}	7.0	-7.0	2.1	6.9	12.1	-10.0	-4.9
Wet bulb air temperature	t_{wb}	5.9	-7.8	1.1	5.9	10.9	-11.0	-5.9

<i>Flow</i>		m^3/h						
Volume flowrate of heat transfer medium. Hot	q_w	1.51	1.50	1.50	1.50	1.50	1.50	1.50

<i>Pressure difference</i>		kPa						
Heat transfer medium, hot	DP_w	-7.4	-7.4	-7.3	-7.4	-7.4	-7.4	-7.4

<i>Electrical power</i>		kW						
Total	P_T	1.952	1.671	1.745	1.733	1.739	1.666	1.655

Calculated quantities

<i>Thermal power</i>		kW						
Total thermal output power to the heat sink	P_{Ihps}	8.797	5.485	6.768	7.550	10.405	4.923	5.823

<i>Coefficient of performance</i>		(-)						
total	COP_{Ihps}	4.51	3.28	3.88	4.36	5.98	2.96	3.52

Correction in accordance with EN 14511

<i>Correction, pump power</i>		W						
Heat transfer medium pump, hot	$P_{epw,s}$	30	30	30	30	30	30	30

<i>Electrical power after correction</i>		kW						
Total	P_E	1.982	1.701	1.775	1.763	1.769	1.695	1.685

<i>Thermal power after correction</i>		kW						
delivered	P_H	8.827	5.515	6.798	7.583	10.435	4.953	5.853

<i>COP after correction</i>		(-)						
Total	COP	4.45	3.24	3.83	4.30	5.90	2.92	3.47

Heat demand of the house and average outlet temperature according to EN14825

T_{biv}	-5°C							
$P_{designh}$	7.24 kW							
P_{house}	kW		6.41	3.90	2.51	1.11	7.24	5.85
T_{out} , average according to eq.15 in 14825				30.0	26.9	23.9		

Appendix 3

Results, space heating performance in accordance to EN 14825, average climate and high temperature application

Operating point		1	A	B	C	D	E	F
	°C	47/55	-/52	38,1/-	33,5/-	28,9/-	-/55	-/48,67
		7/6w	-7/-8w	2/1w	7/6w	12/11w	-10/-11w	-4/-5w

Data collection period	<i>min</i>	70	70	180	70	70	70	70
Transient		No	No	Yes	No	No	No	No

<i>Temperature</i>		°C						
Heat transfer medium, hot, outlet	t_{w2}	55.0	52.0	44.6	41.9	38.8	55.2	48.7
Heat transfer medium, hot, inlet	t_{w1}	47.0	47.0	38.1	33.5	29.0	50.7	43.1
Dry bulb air temperature	t_{a5}	7.0	-7.0	2.1	6.9	12.1	-10.1	-3.9
Wet bulb air temperature	t_{wb}	5.9	-7.9	1.1	5.9	10.9	-11.0	-5.0

<i>Flow</i>		m^3/h						
Volume flowrate of heat transfer medium. Hot	q_w	0.90	0.90	0.90	0.90	0.90	0.90	0.90

<i>Pressure difference</i>		kPa						
Heat transfer medium, hot	DP_w	-2.7	-2.7	-2.7	-2.8	-2.8	-2.7	-2.7

<i>Electrical power</i>		kW						
Total	P_T	2.694	2.219	2.124	2.077	1.956	2.292	2.165

Calculated quantities

<i>Thermal power</i>		kW						
Total thermal output power to the heat sink	P_{Thps}	8.220	5.221	6.778	8.694	10.146	4.631	5.833

<i>Coefficient of performance</i>		(-)						
Total	COP_{hps}	3.05	2.35	3.19	4.19	5.19	2.02	2.69

Correction in accordance with EN 14511

<i>Correction, pump power</i>		W						
Heat transfer medium pump, hot	$P_{epw,s}$	11	11	11	11	11	11	11

<i>Electrical power after correction</i>		kW						
Total	P_E	2.705	2.230	2.135	2.088	1.967	2.303	2.175

<i>Thermal power after correction</i>		kW						
delivered	P_H	8.229	5.232	6.788	8.705	10.157	4.641	5.843

<i>COP after correction</i>		(-)						
Total	COP	3.04	2.35	3.18	4.17	5.16	2.02	2.69

Heat demand of the house and average outlet temperature according to EN14825

T_{biv}	-4°C							
$P_{designh}$	7.59 kW							
P_{house}	kW		6.72	4.09	2.63	1.17	7.59	5.84
T_{out} , average according to eq.15 in 14825				42.0	36.0	30.1		

Appendix 4

Results, space heating performance testing in accordance with EN 14511 and the certification reference HARP

Operating point

	°C	7/6w 30/35	2/1w -/35	7/6w 40/45
Data collection period	<i>min</i>	70	107	70
Transient		No	Yes	No

<i>Temperature</i>	°C			
Heat transfer medium, hot, outlet	t_{w2}	35.0	34.5	45.0
Heat transfer medium, hot, inlet	t_{w1}	30.0	30.6	40.0
Dry bulb air temperature	t_{a5}	7.0	2.1	7.0
Wet bulb air temperature	t_{wb}	5.9	1.1	6.1

<i>Flow</i>	m^3/h			
Volume flowrate of heat transfer medium, Hot	q_w	1.51	1.50	1.48

<i>Pressure difference</i>	<i>kPa</i>			
Heat transfer medium, hot	DP_w	-7.4	-5.3	-6.6

<i>Electrical power</i>	<i>kW</i>			
Total	P_T	1.952	1.810	2.252

Calculated quantities

<i>Thermal power</i>	<i>kW</i>			
Total thermal output power to the heat sink	P_{Hps}	8.797	6.722	8.401

<i>Coefficient of performance</i>	(-)			
total	COP_{Hps}	4.51	3.71	3.73

Correction in accordance with EN 14511

<i>Correction, pump power</i>	<i>W</i>			
Heat transfer medium pump, hot	$P_{epw,s}$	30	24	27

<i>Electrical power after correction</i>	<i>kW</i>			
Total	P_E	1.982	1.834	2.280

<i>Thermal power after correction</i>	<i>kW</i>			
delivered	P_H	8.827	6.746	8.428

<i>COP after correction</i>	(-)			
Total	COP	4.45	3.68	3.70

Appendix 5

List of components

Below information is given by the manufacturer.

<i>Type: Thermia Atec 9</i>		<i>Year of production:</i> 2014
<i>Part</i>	<i>Manufacturer, type</i>	<i>Model number</i>
Compressor:	Copeland	ZH21
Expansion valve:	Danfoss	UKV18051
Evaporator:	Lloyd Coil	4 row
Condenser:	SWEP	B25*40
Refrigerant: (type, charger)	R407C	4.3 Kg
Control system:	Inbuilt controller Software v2.2.1	
Dryer filter:	Danfoss	DMB163s
High pressure switch:	Saginomya	31 bar
Low pressure switch:	Pressure transmitter 0.4 bar(g)	
Fan	EBM-Papst	S3G 500-AF4855

Appendix 6

Photographs




Figure 1 Heat pump, outdoor unit

Appendix 6




Figure 2 Name plate, outdoor unit

Appendix 7

Uncertainty of measurement

The uncertainty of measurement is calculated according EA-4/16 with a coverage factor, $k = 2$. The results from testing are based partly on direct measurements and partly on calculations. The estimates apply to the total uncertainties including both systematic and random uncertainties. Unit terms and designations are as given in Appendix 7.

Measured data

Temperatures

t_{wo}, t_{wi}	$\pm 0.1 \text{ K}$
$t_{wo} - t_{wi}$	$\pm 0.05 \text{ K}$
t_{a5}	$\pm 0.15 \text{ K}$
t_{wb}	$\pm 0.4 \text{ K}$

Differential pressures

Δp_w	$\pm 1 \text{ kPa}$
--------------	---------------------

Flows

q_w	$\pm 1 \%$
-------	------------

Electric Power

P_T	$\pm 0.5 \%$
$P_{auxiliary}$	$\pm 1 \text{ W}$

Table values

Density

ρ_w	$\pm 1 \text{ kg/m}^3$	(source: SP REPORT 1994:01)
----------	------------------------	-----------------------------

Specific heat capacity at constant pressure

c_{pw}	$\pm 10^{-4} \text{ kJ/(kg. K)}$	(source: SP REPORT 1994:01)
----------	----------------------------------	-----------------------------

Calculated data

P_{1hps}, P_H	$\pm 2.4 \%$
COP_{hps}, COP	$\pm 2.5 \%$

Appendix 8

Nomenclature

Designations for EN14825:

SCOP	The units total seasonal coefficient of performance representing the whole heating season
SCOP _{on}	The average seasonal coefficient of performance in active mode (presenting the hours the heat pump's heating performance is activated)
SCOP _{net}	The average seasonal coefficient of performance in active mode excluding electricity consumption from supplementary electric heater, thermostat off, standby, off mode, and crankcase heating mode

P Power

P_{designh} Design load at T_{designh} conditions

T Temperature

T_{designh} Reference design temperature condition for heating (outdoor air temperature)

T_{biv} Bivalent temperature, where the unit is capable of covering 100% of the buildings heating load (outdoor air temperature)

TOL Operation limit temperature

Designations for capacity tests:

Beteckningar

Designations

COP Värmefaktor

Coefficient of performance

COP Värmefaktor; total; rumsuppvärmning; korrigerad enligt EN 14511

Coefficient of performance; total; space heating; corrected according to EN 14511

COP_{hps} Värmefaktor; total. rumsuppvärmning

Coefficient of performance. space heating for heat pump system

P El- och värmeeffekt

Power: electric (active) or thermal

P_E Effekt; el; totalt tillförd till värmepumpsystemet; korrigerad enligt EN 14511

Power; electrical; total input to heat pump system; corrected according to EN 14511

P_H Effekt; värme; från värmepumpsystem till värmesänka. korrigerad enligt EN 14511

Heating capacity; from heat pump system to heat sink; corrected according to EN14511

P_{1hps} Effekt; värme; från värmepumpsystem

Heating capacity; from heat pump

Appendix 8

	till värmesänka	system to heat sink
P_T	Effekt; el; totalt tillförd till värmepumpsystemet	Power; electrical; total input to the heat pump system
q	Volymflöde	Volume flow rate
q_w	Volymflöde; värmeöverförande medium; varm	Volume flow rate; heat transfer medium; warm
t	Temperatur	Temperature
t_{amb}	Temperatur; omgivning	Temperature. ambient
t_{a5}	Temperatur; värmeöverförande medium; kall	Temperature; heat transfer medium; cold
t_w	Temperatur; värmeöverförande medium; varm	Temperature; heat transfer medium; warm
c_p	Specifik värmekapacitet	Specific heat capacity
c_{pw}	Specifik värmekapacitet. värmeöverförande medium; varm	Specific heat capacity; heat transfer medium; warm
Δp	Differenstryck	Differential pressure
Δp_w	Differenstryck; yttre; värmeöverförande medium; varm	Differential pressure; external; heat transfer medium; warm
ρ	Densitet	Density
ρ_w	Densitet. värmeöverförande medium; varm	Density; heat transfer medium; warm

Appendix 8

Index

amb	Omgivning
c	Värmeöverförande medium; kall
def	Avfrostning
e	Elektrisk
h	Uppladdning
hp	Värmepump
hps	Värmepump system
i	In till värmepump
m	Motor; kompressor
max	Maximal
o	Ut från värmepump
p	Pump
s	Tomgång
s	Standardiserad
t	Tappning varmvatten
w	Värmeöverförande medium; varm
wc	Tappvatten; kall
wh	Tappvatten; varm

Indices

Ambient
Heat transfer medium; cold
Defrost
Electrical
Heating up period
Heat pump
Heat pump system
Inlet to heat pump
Motor; compressor
Maximum
Outlet from heat pump
Pump
Stand by
Standardised
Draw off sanitary water; warm
Heat transfer medium; warm
Sanitary water; cold
Sanitary water; hot